

OBIECTIV 8094 EXTINDERE RETEA CANAL MENAJER
 Str.BUNYITAI-Ap.Ion ALEXI,ORADEA
 OBIECT 4.1 RETEA CANALIZARE MENAJERA

LISTA CANTITATILOR DE LUCRARI

DEVIZUL OFERTA 9411
 CATEGORIA DE LUCRARI: COLECTOR STRADAL

pag: 1

Nr. crt	Lucrare Denumire	U/M	Cantitate	Pret unitar Material Manopera Utilaj Transport (lei/UM)	Valoare Material Manopera Utilaj Transport (lei)
0	1	2	3	4	5 - 9

1 1 COLECTOR STRADAL M 203.000

1 TSC03C1 SMC 2.460

SAPAT.MEC.CU EXC.DE 0,41-0,7 MC IN PAM.C
 U UMIDITATE.NATURAL DESC.DEP.TEREN CAT 3
 /

2 TSA18C1 MC 43.400

SAP.MAN.IN URMA EXCAV.MECANICE,GROPI Q.B
 L.FUND.L. EL.PAM.U MID.NAT.F.SPRIJ,ADINC.
 <2,5M,TEREN F.TARE /

3 TSF08B1 MP 609.000

SPRIJ.MAL.CU DULAPI MET.TER.CU IMPING.MA
 RI,LAT.INTR.MAL.<1,5M,AD.0,0-2M;0,05-0,2
 M INTRE DULAPI /

4 ACE08A1 MC 59.600

UMPLUTURA IN SANT.LA COND.DE ALIM.CU APA
 SI CANALIZARE CU: NISIP
 \$/

5 ACA15H1 M 201.000

-100.00/ /
 MONTARE TUBURI DE PRES.DIN POLIEST.ARMAT
 E CU FIBRESTICLA PRIN INFAS.,IN PAM.EXT.
 CLAD.,MF+CEP P,D300 /

6 9125085 M 205.000

Teava PVC cu mufa si garnitura SN8 D=315
 x 9,2 mm
 /

7 ACA17A1 BUC 19.000

-100.00/ /
 PIESA LEGATURA DIN POLIESTERI ARMATE CU
 FIBRE STICLA AVIND GREUTATEA PE BUCATA P
 INA LA INC. 10 KG /

0	1	2	3	4	5 - 9
8	9126182	BUC	19.000		
	Ramificatie redusa canal PVC D=315x160 m m/45ø				
	/				-----
9	ACD04C1	BUC	4.000		
	-100.00/ /				
	MONTAT CAMIN VIZITARE DIN PVC LA CANALE CU D=315 MM				
	/				-----
10	9411628	BUC	4.000		
	Camin monobloc (PEHD) in/Di/out=315/ 600/ 315 mm H=1,9 m				
	/				-----
11	ACD01L1	BUC	4.000		
	CAPAC SI RAMA STAS 2308-81 PENTRU CAMINE CU PIESA SUPORT CAROSABIL IV				
	/				-----
12	DA06B1	MC	193.000		
	STRAT AGREG NAT CILINDRATE CU FUNC REZIS T FILTRANTIZOLAT AERISIRE SI ANTICAP CU ASTER MEC BALAST				
	/				-----
13	DA06A1	MC	34.000		
	STRAT AGREG NAT (BALAST) CILINDR CU FUNCT REZIST FILTRANT IZOL AERISIRE ANTCAP CU ASTERNERE MANUALA				
	/				-----
14	CA01A1	MC	4.720		
	TURNARE BETON SIMPLU IN FUNDATII (CONTINU E, IZOLATE) SI SOCLURI CU VOLUM <3MC				
	/				-----
15	2100933	MC	4.760		
	BETON DE CIMENT B 100/C6 /Bc7,5 (0- 31)				
	/				-----
16	TRA06A15	TO	11.900		
	TRANSPORTUL RUTIER AL BETONULUI-MORTARUL UI CU AUTOBETONIERA DE 5,5MC DIST. =15K M				
	/				-----
17	TRA01A25	TO	587.000		
	TRANSPORT RUTIER AGREGATE DE BALASTIERA DE LA D= 25 KM.				
	/				-----

0	1	2	3	4	5 - 9
---	---	---	---	---	-------

18 TRA01A05P TO 521.000

TRANSPORTUL RUTIER AL PAMINTULUI SAU MOL
OZULUI CU AUTOBASCULANTA DIST.= 5 KM
\$/

19 ACE16A1 M 80.000

MONTAREA PARAPETELOR SI PODETELOR METALI
CE DE INVENTAR LA SANTURI PT.CONDUCTE
\$/

Cheltuieli directe

Materiale	Manopera	Utilaje	Transport	Total
5	6	7	8	9

din care :

- utilaje termice
- utilaje electr.

Alte cheltuieli directe

CAS %
Somaj %
Sanatate %
Fond risc %
Alte cote %

TOTAL CHELTUIELI DIRECTE

Cheltuieli indirecte %
Profit %

TOTAL GENERAL

PROIECTANT :

CONTRACTANT :

SC CONTEMPORAN PROIECT SRL ORADEA

/

OBIECTIV 8094 EXTINDERE RETEA CANAL MENAJER
 Str.BUNYITAI-Ap.Ion ALEXI,ORADEA
 OBIECT 4.1 RETEA CANALIZARE MENAJERA

LISTA CANTITATILOR DE LUCRARI

DEVIZUL OFERTA 9412
 CATEGORIA DE LUCRARI: RACORDURI LA IMOBILE

pag: 1

Nr. crt	Lucrare Denumire	U/M	Cantitate	Pret unitar Material Manopera Utilaj Transport (lei/UM)	Valoare Material Manopera Utilaj Transport (lei)
0	1	2	3	4	5 - 9

1 1 RACORDURI LA IMOBILE BUC 19.000

1 TSC03C1 SMC 0.711

SAPAT.MEC.CU EXC.DE 0,41-0,7 MC IN PAM.C
 U UMIDITATE.NATURAL DESC.DEP.TEREN CAT 3
 /

2 TSA18C1 MC 17.800

SAP.MAN.IN URMA EXCAV.MECANICE,GROPI Q.B
 L.FUND.L. EL.PAM.U MID.NAT.F.SPRIJ,ADINC.
 <2,5M,TEREN F.TARE /

3 ACA15E1 M 114.000

-100.00/ /
 MONTARE TUBURI DE PRES.DIN POLIEST.ARMAT
 E CU FIBRESTICLA PRIN INFAS.,IN PAM.EXT.
 CLAD.,MF+CEP P,D150 /

4 9125059 M 117.000

Teava PVC cu mufa si garnitura SN8 D=160
 x 4,7 mm
 /

5 SB17G1 BUC 19.000

-100.00/ /
 COTURI PVC-U,PT CANALIZARE,CU IMBINARE P
 RIN LIPIRELA 45;67 1/2;87 1/2 GRADE,AVIN
 D D=160 MM /

6 9114787 BUC 19.000

Cot uPVC-KG D=160/45ø
 /

7 ACD04A1 BUC 19.000

-100.00/ -65.00/
 CAMIN VIZITARE STAS 2448-73 CU CAMERA LU
 CRU HC=2M DIN TUB BET.CU CEP SI BUZA LA
 CANALE CU DN 200 /

0	1	2	3	4	5 - 9
8	9123790	BUC	19.000		
	Baza camin PP SG 315 tip 1 D=160 mm, H1=290 mm				
	/				-----
9	9124237	M	11.400		
	Coloana corugata camin SG 315				
	/				-----
10	9124251	BUC	19.000		
	Garnitura etansare pt. camine SG 315				
	/				-----
11	ACD01G1	BUC	19.000		
	-100.00/	/			
	CAPAC SI RAMA STAS 2308-81 PENTRU CAMINE CU PIEASA SUPORT NECAROSABIL TIP I				
	/				-----
12	9124275	BUC	19.000		
	Tub telescopic pt. camine SG 315 H=375 m				
	/				-----
13	9124251	BUC	19.000		
	Garnitura etansare pt. camine SG 315				
	/				-----
14	9124328	BUC	19.000		
	Guler din beton pt. camine SG 315				
	/				-----
15	9124378	BUC	19.000		
	Capac fonta D400 pt. tub telescopic SG 315				
	/				-----
16	ACE09F1	BUC	19.000		
	-100.00/	/			
	MONTAREA ARMATURILOR CU ACTIONARE MANUAL A SAU MECANICA (ROB.VANE VENTILE CLAP.CO MPENS.ETC.)DN: 150 \$/				
	/				-----
17	9116125	BUC	19.000		
	Clapeta antirefulare uPVC-KG D=160				
	/				-----

0	1	2	3	4	5 - 9
---	---	---	---	---	-------

18 ACE08A1 MC 18.300

UMPLUTURA IN SANT.LA COND.DE ALIM.CU APA
SI CANALIZARE CU: NISIP
\$/

19 DA06B1 MC 54.800

STRAT AGREG NAT CILINDRATE CU FUNC REZIS
T FILTRANTIZOLAT AERISIRE SI ANTICAP CU
ASTER MEC BALAST /

20 DA06A1 MC 13.700

STRAT AGREG NAT (BALAST) CILINDR CU FUNCT
REZIST FILTRANT IZOL AERISIRE ANTCAP CU
ASTERNERE MANUALA /

21 TRA01A25 TO 178.000

TRANSPORT RUTIER AGREGATE DE BALASTIERA
DE LA D= 25 KM.
\$/

22 TRA01A05P TO 161.000

TRANSPORTUL RUTIER AL PAMINTULUI SAU MOL
OZULUI CU AUTOBASCULANTA DIST.= 5 KM
\$/

Cheltuieli directe

Materiale	Manopera	Utilaje	Transport	Total
5	6	7	8	9

din care :

- utilaje termice
- utilaje electr.

Alte cheltuieli directe

CAS %
Somaj %
Sanatate %
Fond risc %
Alte cote %

TOTAL CHELTUIELI DIRECTE

Cheltuieli indirecte %
Profit %

TOTAL GENERAL

PROIECTANT :

CONTRACTANT :

SC CONTEMPORAN PROIECT SRL ORADEA /